

**NAGARI GRAM PANCHAYAT**  
**PATHRA :BIRBHUM**

Mail ID - pradhan.nagarigp@gmail.com

Contact: 9732249913

**e-Tender, NIT No-05 /NGP 2022, Dated-15/07/2022**

Percentage rate e-tenders for the under mention works are invited from the experienced and resourceful bidders for execution of the works. The intending tenders should download the detailed tender notice along with tender documents from link <https://wbttenders.gov.in>. The tenders will have to submit their bid online in two folder system containing pre-qualification documents (Technical Bid) in one and (Financial bid) in another.


**Details of work.**

S.I. No	Name of Work	Name of Fund	Amount put to tender(Rs)	Earnest Money (Rs)	Cost of Tender Paper (Rs)	Valid period	Draft in favour of	Executing Agency GP
1	Construction of Concrete drain with soakpit from Kamardanga nichupara Indaratala towards Nurshad khan house at	15th CFC TIED	170000.00	3400.00	250.00	30 days	Proadhan,Nagari Gram Panchayat	Proadhan,Nagari Gram Panchayat

E-Tender may be accepted through portal up to 12.00 pm on 28/07/2022 , Date & time of opening Technical Bid 01/08/2022 at 11.00 am

Date & time of opening Financial Bid 01/08/2022 at 2.00 pm at the office of the Nagari Gram Panchayat. (Following documents should be uploaded as eligibility criteria)

- 1) Pan card
- 2) IT return last three years
- 3) Professional Tax enrollment certificate with current challan.
- 4) G.S.T registration certificate with latest return certificate.
- 5) Credential certificate within the last five year.
- 6) Trade Registration Certificate (2022-23)


  
Pradhan  
Nagari Gram Panchayat  
Pathra (Suri-I) Birbhum

Memo no:- 448 / NGP / 2022      Date:- 15/07/2022

**Copy forwarded for information and with a request for wide publicity to:-**

1. A.E.O. Birbhum Zilla Parishad, Suri , Birbhum.
- 2) Sub- Divisional Officer, Sadar Sub Division, Suri, Birbhum.
- 3) B.D.O , Suri -I Dev. Block, Kalipur Barobagan, Suri, Birbhum.
- 4) Office Notice Board, Nagari G.P.



  
Pradhan  
Nagari Gram Panchayat  
Pathra (Suri-I) Birbhum

**Estimate for Construction of Concrete drain with soakpit from Kamardanga nichupara Indaratala towards Nurshad khan house at Kamardanga (2022-23, SI No-26) of NAGARI GRAM PANCHAYAT of SURI-I DEVELOPMENT BLOCK.**

TOTAL LENGTH OF THE DRAIN = <b>67.4</b> METRE		INNER WIDTH = <b>0.4</b> M	
AV. HEIGHT OF ROAD SIDE BRICK WORK = <b>0.5</b> METRE		AV. HEIGHT OF COUNTRY SIDE BRICK WORK = <b>0.5</b> METRE	
THICKNESS OF BRICK WORK ON ROAD SIDE	0.25 METRE	THICKNESS OF BRICK WORK ON COUNTRY SIDE	0.25 M
THICKNESS OF P.C.C. (1:2:4) BELOW SOLING	0.075 METRE		
TH OF SOLING (S.B.F.) BELOW P.C.C.	0.075 METRE		
THICKNESS OF SAND BELOW SOLING	0.075 METRE		
OFFSET OF CONCRETE ON EACH SIDE	0.025 METRE		
<b>FUND - 15<sup>th</sup> F.C. TIED</b>			

Sl. No.	Description of Item	No	L	B	H	Quantity	Total Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil including removing, spreading or stacking the spoils within a lead of 75 m as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete as per direction of E.I.C.	1	67.4	0.95	0.6	38.418	38.418	m <sup>3</sup>	119.27	4582
2	Filling in foundation or plinth by fine river sand in layers not exceeding 150 mm as directed and consolidating same by thorough saturation with water & ramming complete, including the cost of supply of sand. (Payment to be made on measurement of finished quantity) as per direction of E.I.C.	1	67.4	0.95	0.075	4.80225	4.802	m <sup>3</sup>	572.55	2750
3	Single brick flat soling with 1st class kiln burnt bricks /size picked jhama bricks including ramming and dressing bed to proper level and filling joints with powdered earth or local sand etc all complete as per drawing & direction of E.I.C.		67.4	0.95		64.03	64.030	m <sup>2</sup>	266	17032
4	Nominal Mix M - 15 (1:2:4) Cement concrete with graded trap stone chips (20 mm.size) excluding shuttering and reinforcement, if any, in ground floor as per direction of E.I.C.	1	67.4	0.95	0.075	4.80225	4.802	m <sup>3</sup>	4475.82	21494
5	Brick Work with 1st class bricks of 1:4 cement - sand mortar including the cost of all materials and scaffolding if necessary all complete as per specification and direction of E.I.C.	2	67.4	0.25	0.5	16.85	16.850	m <sup>3</sup>	4444.16	74884
6	Plaster with cement sand mortar(1:4) of 15mm th. Etc. all complete.	1	67.4	1.9		128.06	128.060	m <sup>2</sup>	146.24	18727

	Cement Punning of about 1.5mm brick etc. all complete.						128.060	m <sup>2</sup>	32.76	4195
8	Cement concrete with graded trap stone chips of proportion(1:1.5:3) for reinforced cement concrete works excluding shuttering & reinforcement as per drawing, specification and direction of E.I.C. For R.C.C. Slab	5	0.9	0.9	0.125	0.50625	0.506	m <sup>3</sup>	5155.55	2610
9	Reinforcement for R.C.C. works in all sorts of structure including binding with 16 gauge black annealed wire . . . etc all complete as per direction of E.I.C. of Tor Steel.					40	0.040	MT	54741.47	2190
10	Shuttering works with necessary wooden planks etc all complete.	5	0.9		0.4	1.8	4.050	m <sup>2</sup>	93	377
		5	3.6		0.125	2.25				
11	Display board making with bi-colour oil bound synthetic enamel paints over primer on walls nearer to construction site of size 900mm x 600mm & supply 6 nos colour photographs of (3) three stages (i.e. before, after & at the time of construction) atleast 2nos photos on each stage etc. all complete as per direction of E.I.C.								L.S.	500
									TOTAL = Rs.	149341
									GST @ 12% = Rs	17921
									TOTAL = Rs.	167262
									Cess @ 1% = Rs.	1673
									TOTAL = Rs.	168935
									Contingencies within 3% = Rs.	1065
									GRAND TOTAL = Rs.	170000
<b>(Rupees One Lac Seventy Thousand Only)</b>										

*13/7/2022*

Nirman Sanayak  
Nagari Gram Panchayat

*Bali Buri*

**Pradhan**  
Nagari Gram Panchayat  
Pathra (Suri-I) Birbhum